

### Old State Road Resurfacing - Phase 2

Plymouth East Road to US 224.: 8,000 ft. x 20 ft. (Avg.) = 18,000 SY

*1-1/4" average overlay. 1-1/2" calculated for profile correction*

Ref.	Item	Description	Quant.	Unit	Unit Cost	Total Cost
1	103.5	Premium Contract Bond	1	LS	\$2,500.00	\$2,500.00
2	253	Full Depth Asphalt Repair (4"), as per plan	250	SY	\$75.00	\$18,750.00
3	254	Pavement Planning	1500	SY	\$7.00	\$10,500.00
4	407	Tack Coat @ 0.1 Gal/SY, Non- tracking	2,000	GAL	\$3.00	\$6,000.00
5	441	Asphalt Concrete, Surface Course, Type 1, Scratch/Level, PG64-22, as per plan	100	CY	\$225.00	\$22,500.00
6	441	Asphalt Concrete, Surface Course, Type 1, 1-1/4" Avg., PG64-22, as per plan	750	CY	\$195.00	\$146,250.00
7	614	Maintaining Traffic	1	LS	\$10,000.00	\$10,000.00
8	617	Stabilized Crushed Aggregate (411 berm)	200	Ton	\$55.00	\$11,000.00
9	623	Monument Boxes adjusted to grade	4	EA	\$750.00	\$3,000.00
10	624	Mobilization	1	LS	\$6,000.00	\$6,000.00
11	642	Center Line	2.6	MI	\$1,500.00	\$3,900.00
12	Spec.	Contingencies	1	LS	\$4,600.00	\$4,600.00

**TOTAL = \$245,000.00**

