


Moriah Road Superstructure Replacement

HUR TR165-02.40, SFN 3937682, PID 117439

Installation of Galvanized Superstructure with Wood Decking (28' span x 24' wide)

Ref.	Item	Description	Quant.	Unit	Unit Cost	Total Cost
1	513	Structural Steel Members, Level 1 (interior)	5	Ea.	\$12,000.00	\$60,000.00
2	513	Structural Steel Members, Level 1 (fascia)	2	Ea.	\$15,000.00	\$30,000.00
3	513	Structural Steel Members, Diaphragms (C12x30)	22	Ea.	\$500.00	\$11,000.00
4	513	Structural Steel, Bridge Posts (W6x25)	10	Ea.	\$500.00	\$5,000.00
5	513	Diaphragm Connection Angle (L4"x4"x3/8")	44	Ea.	\$250.00	\$11,000.00
6	513	Expansion Angle Joints, as per plan	1	LS	\$2,500.00	\$2,500.00
7	513	Bearing Plates and Anchor Bolts	1	LS	\$4,000.00	\$4,000.00
8	516	1 1/2" Preformed Expansion Joint Filler, as per plan	100	SF.	\$10.00	\$1,000.00
9	517	Bridge Rail - Tubular Back-up	75	Ft	\$180.00	\$13,500.00
10	606	Guardrail Post, Off Bridge (W6x15)	4	Ea.	\$250.00	\$1,000.00
11	606	Guardrail, Type MGS	75	Ft	\$30.00	\$2,250.00
12	Special	Fasteners & Incidentals	1	LS	\$3,250.00	\$3,250.00
13	Special	Stainless Steel Drip Strip, as per plan	75	Ft.	\$20.00	\$1,500.00
14	Special	Treated Wood Decking, 2"x6"x24'	230	Ea.	\$100.00	\$23,000.00
15	Special	Load Rating Analysis	1	LS	\$1,000.00	\$1,000.00

Project Total = **\$170,000.00**

Lee E. Tansey